SCREENING VARIABILITY REDUCTION CASE STUDY

Our Goal:

To reduce variability in OHP1 and OHP2 screening plants by means of PID tuning and process Control Optimisation.

There were different opportunities, including:

- Increase operator level of comfort with current process control operation by providing improved gridlock protection and better reaction when different control loops take control.
- Tune PID response to compensate recent plant equipment changes.
- Challenge current constraint set points and safely push equipment to be operated to their nominal capacity,
- · Include new constraints into the constraint system

Our Solution:

PID tuning and logic changes were implemented in order to achieve a reduction of variability on the screening plants.

Additional Feedforward logic was included and Gridlocking protection Setpoints were revised.

Group Start logic was fixed on both plants increasing operator's level of confidence with the automatic control.

Unlocked Potential:

There was a significant behaviour change in screening plant output with a reduction of standard deviation and increase of average at the bottleneck.

Plant's throughput Loop (in control 12% of the time) compliance to set point improved 14.31%, and standard deviation reduced 3.51%. Reduced the chance for Gridlocking events.

Total annualized potential capacity increase of ~ 309 ktpa





Wilson Florez Co-founder & Director Principal Process Control Engineer

Key Insight:

Propose Solution

comfort with current process control operation

by improving gridlock

measured annualised

increased of ~309ktpa

potential capacity

protection.

Measure

Tune PID loops.

Increase operator level of

"It was incredibly encouraging working collaboratively with site teams to complete all activities related to this project.

Great support from site's leadership team made the job easier to implement giving in consequence outstanding results."

Identify Opportunities

To reduce variability in OHP1 and OHP2 screening plants

<u>Implement</u>

PID tuning & logic changes were implemented to achieve a reduction on variability

<u>Communicate</u>

Performed across the remote operation centres & site with operations and P&I Engineers